

STINGER[™] 4792 Boom Truck Crane

FEATURES

- 47,000 lb (21 314 kg) maximum lifting capacity
- 101' (30.78 m) maximum tip height
- 144' (43.89 m) maximum tip height with 26-44' (7.92-13.41 m) jib
- 29-92' (8.84-28.04 m) four-section full power fully synchronized boom
- Exclusive color coded boom and load charts
- Easy-to-install optional 26' (7.92 m) one stage or 26-44' (7.92-13.41 m) two stage telescoping jib, man baskets or work platform increase job capacities
- Electronic Load Moment Indicator and anti-two-block device standard
- Externally located planetary rotation drive for easy accessibility for maintenance
- 2-speed planetary winch has 9,600 lb (4 350 kg) maximum permissible 1 part line, 33,600 lb (15 240 kg) breaking strength, 186 ft/min (57 m/min) maximum line speed
- Dual control station with direct mechanically controlled hydraulic system
- 90 gal (342 L) capacity hydraulic tank



Machines shown may have optional equipment.

SPECIFICATION

Boom

29-92' (8.84-28.04 m) four-section full power fully synchronized boom. Patented keel boom design utilizes a keel shaped base plate combined with a deep, four plate boom section to optimize strength / rigidity-to-height ratio. Exclusive, patented color-coded boom and load charts allow the operator to easily determine boom extension, boom angle and load capacity. Maximum tip height with four-section 29-92' (8.84-28.04 m) boom is 101' (30.78 m). Maximum tip height with optional two-stage 26-44' (7.92-13.41 m) jib is 144' (43.89 m).

Winch

Hydraulic winch with gear motor and planetary reduction gearing provides 2speed operation. First layer rope pull of 11,400 lb (5 170 kg). Wire rope size is 9/16" (14 mm) with 33,600 lb (15 240 kg) breaking strength.

Operating Speeds

Mainframe / turret assembly planetary gear rotation provides 180° rotation (370° with optional front bumper outrigger). Swing rotation is 75 seconds. Boom up/down is 41/30 seconds and boom extend/retract is 80/36 seconds.

Hydraulics

Three-section pump allows the operator to perform simultaneous crane operations (winch, boom and swing). Capacities are 32, 17 and 8 gpm (122, 64 and 30 L/m). Hydraulic tank capacity is 90 gpm (342 L/m).

Controls

Fully proportional, excellent metering characteristics for precise boom movements. Independent outrigger controls allow the crane to be stable and level in rigorous working conditions. Load Moment Indication System has audio alarm and functional shut down when operator encounters an overload situation.

Outriggers

Front outriggers are Link-Type. The maximum width over main outrigger pad is 21' 9" (6.62 m), main outrigger spread at maximum ground penetration is 21' 4" (6.51 m).

Rear outriggers are Out & Down. The maximum width over auxiliary outrigger pads is 17' 6" (5.34 m).

Subframe

Single fabricated, closed-box style subframe yields greater strength and rigidity. Wheelbase for standard truck crane mounting configuration is 261" (6.62 m).

OPTIONS AND ACCESSORIES

Terex Stinger offers a wide range of options and accessories to customize your truck crane to your exact needs. These include:

- · Single and two-stage jibs
- Multi-part load blocks
- Main winch with 2 speed motor
- Auxiliary winch
- Rotation-resistant load line
- Heavy duty wood flatbed
- Extra heavy duty wood flatbeds

- Extra heavy duty steel flatbeds
- Radio remote controls
- One-man or two-man baskets
- Self-leveling work platform
- Winch drum tensioner
- Continuous rotation
- Oil cooler

- Single front bumper outrigger (required for 370° or continuous rotation)
- Hydraulic hose reel
- Hydraulic auxiliary tool circuit for cab
- Tool box


STINGER 4792 LOAD RATINGS


Maximum Load Chart in pounds (lbs) with fully extended outriggers

	BOOM LENGTH												
	29 Ft 44 Ft		57 Ft		71 Ft		84 Ft		92 Ft				
OPER. RADIUS (Ft)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	LOADED BOOM ANGLE (DEG)	LOAD RATING (LB)	OPER. RADIUS (Ft)
5	78	47,000*											5
8	71	36,800*	78	20,300*									8
10	67	30,900*	75	20,300*	79	18,400*							10
12	62	26,100*	73	20,300*	77	17,400*							12
14	58	21,900*	70	19,400*	75	16,800*	78	14,600*					14
16	53	18,800*	67	17,300*	73	15,900*	77	13,800*	79	12,300*			16
20	41	14,200*	61	13,900*	68	13,400*	73	12,300*	76	10,900*	78	9,825*	20
25	21	10,400*	53	10,900*	63	10,600*	69	10,400*	73	9,800*	75	9,025*	25
30			45	8,625*	57	8,625*	65	8,425*	69	8,225*	71	7,425*	30
35			34	6,925*	51	6,925*	60	6,925*	66	6,725*	68	6,325*	35
40			19	5,225*	44	5,625*	56	5,625*	62	5,625*	65	5,425*	40
45					36	4,625*	50	4,625*	58	4,625*	61	4,625*	45
50					26	3,725*	45	3,725*	53	3,725*	57	3,725*	50
55	BT	& RN	1 Mod	els 🗌	1	1,225*	38	3,025*	49	3,025*	53	3,025*	55
60							31	2,425*	44	2,425*	49	2,425*	60
65	NOT						21	2,025*	39	2,025*	45	2,025*	65
70	NOTE: STRUCTURAL STRENGTH RATINGS IN CHART ARE INDICATED WITH AN ASTERISK (*)						32	1,525*	40	1,525*	70		
75								25	1,225*	35	1,225*	75	
80						┍┛───			14	825*	28	825*	80

Stowed Jib Deductions (Pounds)

350





Deductions from rated loads for load handling devices BT & RM					
Overhaul Ball:	125 lbs				
1 Tip Load Block:					
2 Tin Load					

Block: 250 lbs

JIB CAPACITIES FOR ALL BOOM LENGTHS								
VERIFY OPERATIONA	L MODE	E SETTIN	g on lm	I DISPL	AY BEFO	RE LIFT	NG WITI	H JIB
Loaded Boom Angle	50°	55°	60°	65°	70°	75°	78°	80°
Retracted 26 ft. Jib	725	1,025	1,525	2,325	3,225	4,325	4,925	5,325
Extended 44 ft. Jib	425	725	1,125	1,525	2,025	2,525	2,825	3,125

500

General Notes

700

- 1. The operator must read and understand the Owner's Manual before operating this crane.
- 2. Positioning or operation of crane beyond areas shown on this chart is not intended or approved except where specified in Owner's Manual.
- 3 Loaded boom angles at specified boom lengths give only an approximation of the operating radius. The boom angle before loading should be greater to account for deflections. Do not exceed the operating radius for rated loads.
- 4. Use rating of next longer boom for boom lengths not shown. Use rating of next greater radius for load radii not shown.
- 5. Boom must be fully retracted when jib is erected before lowering below minimum angle. Retracted jib has no lifting capacity below a 50° boom angle.
- 6. Use rating of next lower boom angle for boom angles not shown on jib load rating chart. 7. Lifting off the main boom point while the swing
- around jib is erected is not intended or approved. 8. Do not lower boom into this area, as hydraulic
- pressure will not allow raising the boom without retracting boom first.
- 9. Crane load ratings on outriggers are based on freely suspended loads with the machine leveled and standing on a firm uniform supporting surface. No attempt shall be made to move a load horizontally on the ground in any direction.
- 10. Practical working loads depend on supporting

surface, wind and other factors affecting stability such as hazardous surroundings, experience of personnel, and proper handling, must all be taken into account by the operator.


300

250

200

- 11. The maximum load which may be telescoped is limited by hydraulic pressure, boom angle, and boom lubrication. It is safe to attempt to telescope any load within the limits of the load rating chart. INFORMATION
- 1. Deductions must be made from rated loads for stowed iib, optional attachments, hooks and loadblocks (see deduction chart). Weights of slings and other load handling devices shall be considered a part of the load.
- 2. Crane load ratings with outriggers are based on outriggers and stabilizers extended and set with all load removed from the carrier wheels.
- 3. Load ratings do not exceed 85% of tipping load.
- DEFINITIONS 1. Operating radius is the horizontal distance from the axis of rotation to the center of the vertical hoist line
- or load hook with load suspended. 2. Loaded boom angle as shown in the Load Ratings Chart is the included angle between the horizontal and longitudinal axes of the boom base after lifting rated load at rated radius.

RANGE DIAGRAM (29 - 92 Ft boom)



		1 Part Line	2 Part Line	3 Part Line	4 Part Line	5 Part Line
		OVERRAUL	ONE SHEAVE LOAD BLOCK	ONE SHEAVE LOAD BLOCK	TWO SHEAVE LOAD BLOCK	AUX SHEAVE SHEAVE LOAD
Winch	Cable	Lift and	Lift and	Lift and	Lift and	Lift and
	Supplied	Speed	Speed	Speed	Speed	Speed
Standard	9/16" Diam.	9,600 lb.	19,200 lb.	28,800 lb.	38,400 lb.	47,000 lb.
Stationary	IWRC XIP	186 fpm*	93 fpm*	62 fpm*	46.5 fpm*	37.2 fpm*
Winch	9/16" Diam.	6,720 lb.	13,400 lb.	20,160 lb.	26,880 lb.	33,600 lb.
	Rotation Resistant	186 fpm*	93 fpm*	62 fpm*	46.5 fpm*	37.2 fpm*

Block Type	Rating
Overhaul Ball	6.5 ton (5.9 mt)
1 Sheave Block	17 ton (15.4 mt)
2 Sheave Block	22.5 ton (20.4 mt)


Overload and anti-two-block systems must be in good operating condition before operating crane. Refer to Owners Manual.

Keep at least 3 wraps of loadline on drum at all times. Use only 9/16" diameter cable with 33,600 lb. breaking strength on this machine.

2 DIFFERENT MOUNTING CONFIGURATIONS

• Behind Cab Mounting Configuration

DIMENSIONAL DATA



CARRIER PROVIDED BY TEREX

STINGER BT4792 - Behind Cab Mounting Configuration

Manufacturer Standard Engine Standard Horsepower Standard Torque Full Tank Capacity

- Standard Transmission
 Speed Standard Transmission
 Max Speed Standard Transmission
 Max Gradeability Standard Transmission
- Optional Transmission
 Speed Optional Transmission
 Max Speed Optional Transmission
 Max Gradeability Optional Transmission


Gross Vehicle Weight Rating Front Axle Weight Rating Rear Axle Weight Rating Front Tires 425 Rear Tires 11F Brakes Exhaust Position

2004 Sterling LT7501 6 x 4 (60 000) Caterpillar C-7 7.2 L I-6 300 hp @ 2,200 rpm 860 lb. Ft. @ 1,440 rpm 60 gal (227 L)

> Eaton Fuller RT-8908LL Manual 10-speed 74 mph (120 km/h) 54%

> > Allison Automatic 6-speeds 74 mph (120 km/h) 17%

60,000 lb (27 210 kg) 20,000 lb (9 067 kg) 40,000 lb (18 144 kg) 425/65R 22.5 Michelin XZY (20 ply) 11R 22.5 Michelin XDE M/S (14 ply) Air, Hydraulic Anti-Lock System Vertical Right Side



Included Options:

Fuel tank (60 gal-227L) Power steering Electric Horn Factory A/C Power Port (Cigar lighter) AM/FM Radio w/ Clock Dual West Coast Stainless Standard Factory Warranty Dual West Coast Stainless Standard Factory Warranty

CHASSIS RECOMMENDATIONS-MINIMUM REQUIREMENT

STINGER BT4792 - Behind Cab Mounting Configuration


Combined Axle Weight Rating Front Axle Weight Rating Rear Axle Weight Rating Wheel base Cab to Axle Afterframe Frame Section Modulus RBM per Frame Rail Frame Height (Unloaded) Exhaust Position 60,000 lb (27 210 kg) 20,000 lb (9 067 kg) 40,000 lb (18 144 kg) 261" (6.62 m) 192" (4.87 m) 114" (2.89 m) 30.0 in³ (491 cm³) 1,860,000 in/lb (32 950 kg/m) 40" (7.62 m) Vertical Right Side

STINGER[™] 4792 Boom Truck Crane

2 DIFFERENT MOUNTING

• Rear Mount Configuration

DIMENSIONAL DATA



CARRIER PROVIDED BY TEREX

STINGER RM4792 - Rear Mount Configuration

Manufacturer	2004 Sterling LT7501 6 x 4 (60 000)				
Standard Engine	Caterpillar C-7 7.2 L I-6				
Standard Horsepower	300 hp @ 2,200 rpm				
Standard Torque	860 lb. Ft. @ 1,440 rpm				
Full Tank Capacity	60 gal (227 L)				
Standard Transmission	Eaton Fuller RT-8908LL				
Speed Standard Transmissi	on Manual 10-speed				
Max Speed Standard Trans					
Max Gradeability Standard	,				
· Ontional Transmission	Allicon				
Optional Transmission Speed Optional Transmission	Allison Automatic 6-speeds				
Speed Optional Transmission Max Speed Optional Transm					
Max Gradeability Optional T					
Max Gradeability Optional 1					
Gross Vehicle Weight Rating					
Front Axle Weight Rating	20,000 lb (9067 kg)				
Rear Axle Weight Rating	40,000 lb (18 144 kg)				
Front Tires	425/65R 22.5 Michelin XZY (20 ply)				
Rear Tires	11R 22.5 Michelin XDE M/S (14 ply)				

Included Options:

Fuel tank (60 gal-227L) Power steering Electric Horn Factory A/C Power Port (Cigar lighter) AM/FM Radio w/ Clock Dual West Coast Stainless Standard Factory Warranty

CHASSIS RECOMMENDATIONS-MINIMUM REQUIREMENT

STINGER RM4792 - Rear Mount Configuration

Combined Axle Weight Rating Front Axle Weight Rating Rear Axle Weight Rating Wheel base Cab to Axle Afterframe Frame Section Modulus RBM per Frame Rail Frame Height (Unloaded) Exhaust Position 60,000 lb (27 210 kg) 20,000 lb (9 067 kg) 40,000 lb (18 144 kg) 261" (6.62 m) 192" (4.87 m) 114" (2.89 m) 30.0 in³ (491 cm³) 1,860,000 in/lb (32 950 kg/m) 40" (7.62 m) Vertical Right Side

For more information, product demonstration, or details on purchase, lease and rental plans, please contact your local Terex Cranes dealer.

Simple, available and

cost effective[™]

Brakes

Exhaust Position

We reserve the right to amend these specifications at any time without notice. The only warranty applicable is our standard written warranty applicable to the particular product and sale. We make no other warranty, expressed or implied.



Waverly Operations 106 12th Street S.E. Waverly, IA 50677-9466 USA TEL: (319) 352-3920 FAX: (319) 352-5727 E-MAIL: inquire@terexwaverly.com WEB: http://www.terex.com Litho in U.S.A.

Air, Hydraulic Anti-Lock System

Vertical Right Side